



## Schedule 10 Sprinkler Pipe "Hot Dipped Galvanized"

Youngstown Tube manufactures Schedule 10 galvanized pipe in sizes 1 ¼" thru 6" using only **high quality domestic** steel coils. This ensures a uniform superior product for roll grooving, welding or plain end uses. Youngstown Tube's schedule 10 pipe is produced under ASTM A135/A795 Type E, Grade A, NH standards. Every piece is Eddy-Current tested and conforms to internal SPC testing and recording.

Youngstown Tube Schedule 10 galvanized steel sprinkler pipe is hot dip galvanized coated to meet ASTM A123 standards. A highly visible weatherproof sticker is applied to each piece of pipe and ready for immediate shipment.

**Approvals:** UL Listed and CUL Listed

Youngstown Tube schedule 10 pipe meets the rigorous testing and certification processes of Underwriters Laboratory for steel sprinkler pipe with working pressures of 300 psi or less and can be used in wet, dry, deluge and preaction systems.

### Schedule 10 Galvanized

Pipe Size	Pipe OD	Pipe ID	Nominal Wall	Weight per Foot	Standard Length	Pieces per Bundle	Feet per Bundle	Weight per Bundle
1 ¼	1.660	1.442	.109	1.92	21	61	1,281	2,454
1 ½	1.900	1.682	.109	2.20	21	44	924	2,035
2	2.375	2.157	.109	2.79	21	37	777	2,170
2 ½	2.875	2.635	.120	3.72	21	37	777	2,887
3	3.500	3.260	.120	4.56	21	24	504	2,298
4	4.500	4.260	.120	5.90	21	19	399	2,355
6	6.625	6.357	.134	9.72	21	10	210	2,042

Warning: Schedule 10 pipe can not be threaded or cut-grooved!

Youngstown Tube Company  
401 Andrews Avenue  
Youngstown, Ohio 44505  
1-866-The-Tube  
www.youngstowntube.com

Project:  Contractor:

Submitted By:  Date Submitted: