



## Schedule 40 Sprinkler Pipe "Hot Dipped Galvanized"

Youngstown Tube manufactures Schedule 40 galvanized pipe in sizes 1" thru 2" using only **high quality domestic** steel coils. This ensures a uniform superior product for roll grooving, welding or plain end uses. Youngstown Tube's schedule 40 pipe is produced under ASTM A135/A795 Type E, Grade A, NH standards. Every piece is Eddy-Current tested and conforms to internal SPC testing and recording.

Youngstown Tube Schedule 40 galvanized steel sprinkler pipe is hot dip galvanized coated to meet ASTM 123 standards. Each piece of galvanized has a continuous black stencil and is ready for immediate shipment.

**Approvals:** UL Listed, CUL Listed, FM Approved

Youngstown Tube schedule 40 pipe meets the rigorous testing and certification processes of Underwriters Laboratory for steel sprinkler pipe with working pressures of 300 psi or less and can be used in wet, dry, deluge and preaction systems.

### Schedule 40 Hot Dipped Galvanized

Pipe Size	Pipe OD	Pipe ID	Nominal Wall	Weight per Foot	Standard Length	Pieces per Bundle	Feet per Bundle	Weight per Bundle
1	1.315	1.049	.133	1.76	21	70	1,470	2,587
1 1/4	1.660	1.380	.140	2.37	21	51	1,071	2,538
1 1/2	1.900	1.610	.145	2.84	21	44	924	2,624
2	2.375	2.067	.154	3.80	21	30	630	2,394

Youngstown Tube Company  
401 Andrews Avenue  
Youngstown, Ohio 44505  
1-866-The-Tube  
[www.youngstowntube.com](http://www.youngstowntube.com)

Project:

Contractor:

Submitted By:

Date Submitted: